## MYSORE DIVISION.

ADVERTISEMENTS.

*The 19th September* 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 5th October 1887, for constructing a new Siladar Line at Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 20 in cash or Government promissory notes as earnest money and be superscribed "Tender for constructing a new Siladar Line at Mysore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for constructing a new Siladar Line at Mysore.

| Items of Work. | Per | Quantity. | Rate. | Cost. | Total. |
|---|---|---|---|---|---|
| Excavation .. .. .. | C. Yd. | 326 | | | |
| Rough stone in mud .. .. | Do | 326 | | | |
| Burnt brick in mud .. .. .. | C. Ft. | 2,748 | | | |
| Half burnt and half raw brick in mud .. | Do | 1,568 | | | |
| Raw brick in mud .. .. .. | Do | 8,492 | | | |
| Burnt brick in chunam .. .. | Do | 1,425 | | | |
| Rough plastering 1 coat with chunam .. | Sq. | 45·66 | | | |
| Mud plastering .. .. | Do | 378·95 | | | |
| Slab stones over doors and windows .. | S. Ft. | 503 | | | |
| Mud wall .. .. .. | C. Ft. | 10,731 | | | |
| Coping with tiles set in mortar .. .. | R. Ft. | 1,259 | | | |
| Wood work (Honne) .. .. .. | C. Ft. | 390 | | | |
| Doors and windows .. .. .. | S. Ft. | 860 | | | |
| Roofing with honne reepers and 2nd class Mangalore tiles .. .. | Sq. | 88·65 | | | |
| Whitewashing .. .. .. | Do | 385·06 | | | |
| Color washing .. .. .. | Do | 44·15 | | | |
| Mangalore ventilating tiles .. .. | Each. | 80 | | | |
| Flooring with gravel .. .. .. | C. Yd. | 122 | | | |

*The 20th September* 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 14th October 1887, for bridging the 1st section of Hunsur-Begur road.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore, between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. The bridge in 18th mile should be completed by the end of May 1889 and the rest in November 1888.

5. The intending competitors may tender for any or all the bridges.

6. Each tender must be accompanied by a deposit of Rs. 60 or Rs. 20 for each bridge in cash or Government promissory notes, as earnest money, and be superscribed "Tender for bridging the 1st section of Hunsur-Begur road," in default of which, tenders will be rejected.

7. The final acceptance of any tender will rest with the Secretary, Public Works Department, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

8. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

9. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

10. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities of bridging the 1st section of Hunsur-Begur road.

| Items of Work. | Per | Bridge in 18th mile. | Bridge in 14th mile. | Bridge in 9th mile. | Total. | Rate. | Amount. | Remarks. |
|---|---|---|---|---|---|---|---|---|
| Excavation .. .. | C. Yd. | 340 | 284 | 194 | 818 | | | |
| Concrete .. .. | C. Ft. | 1,253 | 1,240 | 819 | 3,312 | | | |
| Stone in surki mortar .. | Do | 9,858 | .. | 3,925 | 13,783 | | | |
| Do do .. | Do | .. | 13,948 | .. | 13,948 | | | |
| Brick in surki mortar .. | Do | 12,140 | 9,335 | .. | 21,475 | | | |
| Do do .. | Do | .. | .. | 404 | 404 | | | |
| Arch work .. .. | Do | 3,534 | 2,023 | .. | 5,557 | | | |
| Cut stone work .. .. | Do | 240 | 204 | 250 | 694 | | | |
| Plastering .. .. | Sq. | 51·06 | 35·11 | 9·61 | 93·78 | | | |
| Pointing .. .. | Do | 10·60 | 14·66 | 10·71 | 41·97 | | | |
| Slab stones .. .. | S. Ft. | .. | .. | 1,187 | 1,187 | | | |
| Cornice.. .. | R. Ft. | 242 | 190 | .. | 432 | | | |
| Metalling .. .. | C. Yd. | 35 | 29 | 23 | 87 | | | |
| Gravelling .. .. | Do | 367 | 451 | 113 | 931 | | | |
| Guard stones .. .. | Each. | 4 | .. | .. | 4 | | | |
| Do .. .. | Do | .. | 4 | 4 | 8 | | | |
| Earthwork .. .. | C. Yd. | 3,511 | 10,221 | 1,462 | 15,194 | | | |
| Turfing .. .. | Sq. | 112·90 | 335·84 | 71·15 | 519·89 | | | |
| Iron pipes for rain water .. | No. | 6 | 6 | 8 | 20 | | | |
| Clearing site and breaching rock .. | L. S. Rs. | | | | | | | |
| Clearing jungle .. .. | Do | | | | | | | |
| Baling water .. .. | Do | | | | | | | |
| Forming road .. .. | Do | | | | | | | |
| Centering .. .. | Do | | | | | | | |

V. H. KARVE,
*Executive Engineer.*

362



## SHIMOGA DIVISION.

ADVERTISEMENTS.

*The 21st September* 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 15th October 1887, for constructing a bridge of 4 arches 40′ span over Kumudvati near Shikarpur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1890.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes as earnest money, and be superscribed "Tender for constructing a bridge of 4 arches 40 feet span over Kumudvati near Shikarpur," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

| Items of Work. | Per | Quantity. | Rate. |
|---|---|---|---|
| Earthwork, cutting soft rock .. .. .. | C. Yd. | 1,507 | |
| Do sand & shingle and water .. .. .. | " | 10,976 | |
| Do excavation, soft rock .. .. .. | " | 161 | |
| Do sand and shingle, 1st 6ft. .. .. .. | " | 2,863 | |
| Do do 2nd 6ft. .. .. .. | " | 1,417 | |
| Do do 3rd 6ft. .. .. .. | " | 583 | |
| Baling water, lump sum .. .. .. .. | .. | Rs. | |
| Coffer dam and shoring .. .. .. .. | L. S. Rs. | .. | |
| Training bank .. .. .. .. | .. | Rs. | |
| Stone in surki mortar foundation .. .. .. | C. Ft. | 28,566 | |
| Stone in mortar superstructure .. .. .. | " | 44,041 | |
| Archwork stone in mortar ring pins .. .. .. | " | 1,269 | |
| Do shuting .. .. .. | " | 5,922 | |
| Centerings .. .. .. .. .. | Each. | 4 | |
| Cornicing and coping .. .. .. .. | C. Ft. | 1,416 | |
| Concrete work .. .. .. .. .. | C. Ft. | 205 | |
| Pointing with mortar .. .. .. .. | Sq. | 169·11 | |
| Drainage pipes .. .. .. .. | No. | 19 | |
| Guard stones .. .. .. .. | No. | 8 | |
| Earth filling foundation and sides with good earth .. .. | C. Yd. | 7,827 | |
| Do approaches .. .. | " | 3,627 | |
| Do and cutting side drains .. | " | 4,599 | |
| Turfing .. .. .. .. .. | Sq. | 306·48 | |
| Metalling .. .. .. .. .. | C. Yd. | 129 | |
| Gravelling .. .. .. .. .. | " | 708 | |
| Dressing skew backs .. .. .. .. | L. S. Rs. | Rs. | |
| Hatting .. .. .. .. .. | " | .. | |

*The 21st September* 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 15th October 1887, for the construction of the Sogal Anicut and Channels in